



NOTES:

1. ALL NUTS, BOLTS, PUMP CABLE HANGER AND ASSOCIATED HARDWARE TO BE STAINLESS STEEL, 316.
2. CONTROL PANEL TO BE FABRICATED AND INSTALLED PER SARASOTA COUNTY'S LATEST STANDARD FABRICATION AND INSTALLATION PLANS FOR SCADA AND CONTROL PANELS (DUPLEX AND/OR TRIPLEX). BOTTOM OF CONTROL AND RTU PANELS TO BE SET ABOVE 100 YEAR FLOOD ELEVATION.
3. FULL GUIDE BRACKETS TO SUPPORT STANDPIPE.
4. ELECTRICAL CONDUIT SHALL BE POSITIONED IN WET WELL CLOSEST TO THE PANELS.
5. STAINLESS STEEL BASE PLATE SHALL BE INSTALLED UNDER BASE ELBOWS.
6. WIRES IN WET WELL SHALL NOT INTERFERE WITH THE PULLING OF PUMPS.
7. ALL STEEL 3 INCH CLEAR OF ANY EXPOSED SURFACE
8. 1 INCH CHAMFER ON ALL EXPOSED EDGES
9. HATCH COVER TO BE CENTERED OVER THE PUMPS AS RECOMMENDED BY PUMP MANUFACTURER
10. LIFT STATION WET WELL SHALL BE MANUFACTURED WITH AN APPROVED LINER (SEE ITEM 1 DESCRIPTION)
11. THE PANEL AND PIPING LOCATIONS ARE SUBJECT TO CHANGE IF CONDITIONS REQUIRE IT.

N.T.S.