



GENERAL NOTES:

1. WIRES IN WET WELL SHALL NOT INTERFERE WITH THE PULLING OF PUMPS.

KEY NOTES:

1. FLOAT RACK SHALL BE 4 INCHES FROM TOP OF LID.
2. 316 S.S. STRAPS SECURED TO STRUCTURE WITH 316 S.S. FASTENERS AT 4 FOOT INTERVALS (2 MIN).
3. 2 INCH RAIL SHALL BE WELDED 316L S.S.
4. NEOPRENE PRE-FORMED BOOT CONFORMING TO ASTM C-293 STANDARD WITH SS BAND.

5. BASE ELBOW AND INTERIOR D.I.P. TO BE EPOXY LINED AND COATED. BASE PLATE SHALL BE SIZED TO INCLUDE THE ENTIRE PUMP ASSEMBLY INCLUDING THE BASE ELBOW, AND DESIGNED BY THE ENGINEER IN CONSULTATION WITH THE PUMP MANUFACTURER.

REFER TO SEWER DWG NO.14

N.T.S.