VALVE PIT DETAILS (1) - 3 PIECE

VACUUM DETAIL

IN CONSIDERATION OF THE RECEIPT OF THIS DOCUMENT, THE RECIPIENT AGREES NOT TO REPRODUCE, COPY, USE, OR TRANSMIT THIS DOCUMENT AND/OR THE INFORMATION THEREIN CONTAINED IN WHOLE OR IN PART, OR TO SUFFER SUCH ACTION BY OTHER, FOR ANY PURPOSE EXCEPT WITH THE WRITTEN PERMISSION OF ARYAC, INC. AND DIRTHER AGREES TO SURRENDER SAME TO AIRVAC, INC. UPON DEMAND.

<u>N</u>

REVISIONS

DATE

PITS

SD-1F

3 PIECE V 6" MN. LVE PIT BEDDING AND BACKFILL 4'-5" (MINIMUM) TYPICAL VALVE PIT ASSEMBLY O CONGRETE COLLARS REQUIRED IN TRAFFIC AREAS, SEE ENGINEER'S SPECIFICATIONS FOR DEFINITION OF 'TRAFFIC AREAS' AS WELL AS THE DESIGN DETAILS OF THE COLLAR FINISHED GRADE COMPACTED GRANULAR BEDDING FROM BOTTOM OF EXCAVATION TO CENTER LINE OF GRAVITY STUB-OUT IN SUITABLE MATERIAL SUCH AS #57 STONE, CRUSHED SEA SHELL, "PE" GRAVEL, DO NOT BED IN OTHER MATERIAL WITHOUT AIRVAC APPROVAL COMPACTED SELECT FILL
MATERIAL WITH MINIMUM
DENSITY OF 110 LBS PER
CUBIC FOOT SAND OR OTHER SUITABLE FILL MATERIAL, MAY BE THE SAME AS ABOVE ANTI-BUOYANCY COLLAR UNDISTURBED SOIL AIRIAC ACUUM DETAIL IO. VP-6F









